# HITACHI

KAOHSIUNG HITACHI ELECTRONICS CO.,LTD P.O. BOX 26-27 2,13TH EAST ST. K.E.P.Z. KAOHSIUNG TAIWAN R.O.C. TEL:(07) 8215811 (7 LINE) FAX:(07) 8215815

FOR MESSRS:

ELECTRONICS CO.,LTD.

DATE: May.28,2007

# CUSTOMER'S ACCEPTANCE SPECIFICATIONS ST12Q01L6ALZZ

CONTENTS

No.	ITEM	SHEET No.	PAGE
1	COVER	7B64PS 2701-ST12Q01L6ALZZ-2	1-1/1
2	RECORD OF REVISION	7B64PS 2702-ST12Q01L6ALZZ-2	2-1/1
- 3	GENERAL SPECIFICATIONS	7B64PS 2703-ST12Q01L6ALZZ-2	3-1/1
4	ABSOLUTE MAXIMUM RATINGS	7B64PS 2704-ST12Q01L6ALZZ-2	4-1/1
5	ELECTRICAL CHARACTERISTICS	7B64PS 2705-ST12Q01L6ALZZ-2	5-1/2~2/2
6	OPTICAL CHARACTERISTICS	7B64PS 2706-ST12Q01L6ALZZ-2	6-1/3~3/3
7	BLOCK DIAGRAM	7B64PS 2707-ST12Q01L6ALZZ-2	7-1/1
8.	INTERFACE TIMING CHART	7B64PS 2708-ST12Q01L6ALZZ-2	8-1/4~4/4
9	OUTLINE DIMENSIONS	7B63PS 2709-ST12Q01L6ALZZ-2	9-1/1
10	APPEARANCE STANDARD	7B64PS 2710-ST12Q01L6ALZZ-2	10-1/3~3/3
11	PRECAUTION IN DESIGN	7B64PS 2711-ST12Q01L6ALZZ-2	11-1/3~3/3
12	DESIGNATION OF LOT MARK	7B64PS 2712-ST12Q01L6ALZZ-2	12-1/1
13	PRECAUTION FOR USE	7B64PS 2713-ST12Q01L6ALZZ-2	13-1/1
:			

<sup>\*</sup> When product will be discontinued, customer will be informed by HITACHI with twelve months prior announcement.

ACCEPTED BY:

PROPOSED BY:

MACHING HITACHI

Sh.

7B64PS 2701-ST12Q01L6ALZZ-2

PAGE 1-1/1

No.

# RECORD OF REVISION

· (						<u> </u>					
DATE	SHEET No.		SU	MMARY							
May.28,'07	7B64PS 2704 – ST12Q01L6ALZZ-2 PAGE 4 - 1/1	4.2 ENVIRONMENTAL ABSOLUTE MAXIMUM RATINGS Added Operating Life: (40,000h)									
	7B64PS 2705 – ST12Q01L6ALZZ-2		5.2 ELECTRICAL CHARACTERISTICS OF LED BACKLIGHT								
	PAGE 5 - 2/2		ITEM	М	IN. TYP.	MAX.					
•		Power S	upply Voltage for L	ED (4	.8) (5)	(5.2)					
		Power Supp	ly Current for LED	(Note1)	- (140)						
				<b>↓</b>							
7			ITEM	M	IN. TYP.	MAX.					
		Power S	Supply Voltage for L	ED 4	.8 5	5.2					
		Power Supp	ly Current for LED	(Note 1)	_ (80)	<u>-</u> .					
. 1	7B64PS 2712 – ST12Q01L6ALZZ-2 PAGE 12 - 1/1	Allowate 40 Alloward 10 20 Corrent 10 20 Alloward 10 Alloward 20 A	t Temperature vs. sole Forward Current  40 60 80 100  Temperature Ta(°C)  TION OF LOT	₹	Ambient Tempera Allowable Forward  30 0 30 60 Ambient Temperature	90 120 • Te(C)					
		INLV NO.	I I LIVI	LOT NO.	CONTRO						
			-		0000	01~					
				<b>↓</b>							
		REV No.	ITEM	LOT No.	PRODU CONTR	*					
,		-	-		0000						
		A	Operating Life (40,000h)	7062T	0000	01~					

KAOHSIUNG HITACHI			Sh.			
ELECTRONICS CO.,LTD.	DATE	May.28,'07	Nio	7B64PS 2702-ST12Q01L6ALZZ-2	PAGE	2-1/1
LEECTROMICS CO.,ETD.		<u> </u>	INO.	· ·		• •

## 3. GENERAL SPECIFICATIONS

(1) Part Name ST12Q01L6ALZZ

(2) Module Size 129.6(W)mm x 92.6(H)mm x 7.5(D)mm

(3) Effective Area 100(W)mm min. x 75.5(H)mm min.

(4) Dot Size 0.285(W)mm x 0.285(H)mm

(5) Dot Pitch 0.3(W)mm x 0.3(H)mm

(6) Dot Number 320 (W) x 240 (H)

(7) Duty Ratio 1/240

(8) LCD Type Transflective type F-B / W STN

The upper polarizer is Glare Type.

(9) Viewing Direction 6 O'clock

(10) Viewing Angle Wide Viewing Angle

(11) Operating Temperature Wide Temperature Range

(12) Backlight Type LED(Color : white)

(13) Weight (110g)

#### 4. ABSOLUTE MAXIMUM RATINGS

#### 4.1 ELECTRICAL ABSOLUTE MAXIMUM RATINGS.

VSS=0V:STANDARD

ITEM	SYMBOL	MIN.	MAX.	UNIT	COMMENT
Power Supply for Logic	VDD-VSS	0	6.5	V.	
Power Supply for LC Drive	VDD-VEE	0	27.5	·V	
Input Voltage	Vi	-0.3	VDD+0.3	V	(Note 1)
Input Current	li li	0	1	Α	
Static Electricity	-	·-	100	_	(Note 2)

Note 1: DOFF, FLM, CL1, CL2, D0~D3.

Note 2: Make certain you are grounded when handling LCM.

#### 4.2 ENVIRONMENTAL ABSOLUTE MAXIMUM RATINGS.

ITEM	OPERATING		ST	ORAGE	COMMENT	
	MIN.	MAX.	MIN.	MAX.	·	
Ambient Temperature	-20°C	70°C	-30°C	80℃	(Note 2,3,6)	
	:	(Note 5)				
Humidity	(N	ote 1)	(N	lote 1)	Without Condensation	
		2.45m/s <sup>2</sup>		11.76m/s <sup>2</sup>		
Vibration	-	(0.25G)	-	(1.2G)	(Note 4)	
•	*,			(Note 5)		
		29.4m/s <sup>2</sup>		490.0m/s <sup>2</sup>		
Shock	-	(3 G)	_	(50 G)	X · Y · Z Directions	
				(Note 5)		
Corrosive Gas	Not Aco	ceptable	Not Ac	ceptable		
Operating Life	(40	(40,000 h) (Note 7)			A+ 25°C 1 =90mA may	
(Note 8)				-	At 25℃ , I <sub>LED</sub> =80mA max	
Note 1 - To < 40°C + 950/ D	11					

Note 1 : Ta ≤ 40°C : 85%RH max.

Ta>40°C: Absolute humidity must be lower than the humidity of 85%RH at 40°C.

Note 2: Ta at  $-20^{\circ}$ C ---< 48h, at  $60^{\circ}$ C ---< 168h.

Note 3: Background color changes slightly depending on ambient temperature.

This phenomenon is reversible.

Higher LCD driving voltage is needed while operating at 0°C.

Note 4: 5Hz~100Hz(Except resonance frequency and X, Y, Z each direction within 1h)

Note 5: This module should be operated normally after finish the test.

Note 6: The response time will be slower under low temperature.

Note 7: When brightness reached 50% of initial brightness.

Note 8: Life time is estimated data.

KAOHSIUNG HITACHI		NA 00 207	Sh.	ZDC4DC 0704 CT40004LCAL 77.0	DACE	1 4 14
ELECTRONICS CO.,LTD.	DATE	May.28,'07	No.	7B64PS 2704-ST12Q01L6ALZZ-2	PAGE	4-1/1

# 5. ELECTRICAL CHARACTERISTICS

# 5.1 ELECTRICAL CHARACTERISTICS

ITEM	SYMBOL	CONDITION	MIN.	TYP.	MAX.	UNIT
Power Supply Voltage for Logic	VDD-VSS	_	3.0	5.0	5.25	٧
Power Supply Voltage For LC Driving	VEE-VSS	-	-	-22.0	-	٧
Input Voltage	Vi	H LEVEL	0.8VDD		VDD	- V
Note 1	VI	L LEVEL	0	-	0.2VDD	V.
Power Supply Current for Logic Note 2	IDD	VDD-VSS=5.0V VEE-VSS=-22.0V	<b>-</b>	8.0	-	mA
Power Supply Current For LC Driving Note 2	IEE	VDD-VSS=5.0V VEE-VSS=-22.0V	<u>-</u>	6.0	-	mA
Recommended LC		Ta=-20°C , <i>φ</i> =0°	-	-	-	V
Driving Voltage	VDD-VEE	Ta=25℃, <i>φ</i> =0°	<u>-</u> *,	(23.0)	~	V
Note 4		Ta=70℃ , <i>φ</i> =0°	-		-	V
Frame Frequency	fFLM	-	70	_	(140)	Hz

Note 1: DOFF, FLM, CL1, CL2, D0~D3.

Note 2: fFLM=75HZ

VDD-VEE=23.0V,Ta=25℃.

Note 3: Recommended LC driving voltage fluctuate about ±1.0V by each module. Test pattern is all "Q"

Note 4: Need to make sure of flickering and rippling of display when setting the frame frequency in your set.

KAOHSIUNG HITACHI			Sh.	7D0 4D0 6705 074060 4 04 77 0 DA 05 F 44	$\Box$
ELECTRONICS CO.,LTD.	DATE	May.28,'07	No.	7B64PS 2705-ST12Q01L6ALZZ-2   PAGE   5-1/2	<u> </u>


# 5.2 ELECTRICAL CHARACTERISTICS OF LED BACKLIGHT


Ta=25°C (Backlight on)

ITEM	SYMBOL	CONDITION	MIN.	TYP.	MAX.	UNIT
Power Supply Voltage for LED	VLED	<u>-</u>	4.8	5	5.2	٧
Power Supply Current for LED (Note 1)	ILED	<del>-</del> .	- -	(80)	•	mA

Note 1: The ILED changes depending on ambient temperature.

Ambient Temperature vs.
Allowable Forward Current For LED





KAOHSIUNG HITACHI	D 4 TF	May 00 107	Sh.	700400	0705 074000410			
KAOHSIUNG HITACHI ELECTRONICS CO.,LTD.	DATE	May.∠8, 07	No.	/B64PS	2705-S112Q01L6	ALZZ-2	PAGE	5-2/2

# 6. OPTICAL CHARACTERISTICS


## 6.1 OPTICAL CHARACTERISTICS


Ta=25 °C (Backlight on)

ITEM	SYMBOL	CONDITION	MIN.	TYP.	MAX.	UNIT	NOTE	
Viewing Area	фкк-фғ	K≧2.0	_	80		dog	1,2	
	фкт-фь	N≦2.U		90	. ' -	deg		
Contrast Ratio	K	φ=0°, θ=0°	-	(5)	-	-	3,5,6	
Response Time (Rise)	tr	φ=0°, θ=0°	_	(280)	-	ms	4	
Response Time (Fall)	tf	φ=0°, θ=0°	. 🖶	(280)	-	ms	4	

(Measurement condition : HITACHI standard) Note 2~7 : See next page.


Note 1: Definition of Viewing Angle






LEFT-RIGHT Direction

**REAR-FRONT Direction** 






\* The viewing direction of this product is 6 O'clock. So  $\phi_F > \phi_{RR}$ 

KAOHSIUNG HITACHI		May 20 107	Sh.	7D04D0 0700 07400041 0A1 77 0	D40E	2 4 12
ELECTRONICS CO., LTD.	DATE	Iviay.20, 07	No.	7B64PS 2706-ST12Q01L6ALZZ-2	PAGE	6-1/3

Note 2 : Definition of viewing angle  $\phi_{RR}$  and  $\phi_F$  ,  $\phi_{RT}$  and  $\phi_L$ 




Viewing Angle


Contrast ratio K vs viewing angle φ

Note 3 : Definition of contrast "K"


K= Brightness on selected dot (B1)

Brightness on non-selected dot (B2)





Note 4: Definition of optical response time



KAOHSIUNG HITACHI	DATE	May 28 '07	Sh.	7B64PS 2706-ST12Q01L6ALZZ-2	PAGE	6-2/3
ELECTRONICS CO.,LTD.	DAIL	Iviay.20, 07	No.	7664PS 2706-STIZQUIL6ALZZ-Z	PAGE	b-2/3


#### 6.2 OPTICAL CHARACTERISTICS OF BACKLIGHT

(Backlight ON)


ITEM	MIN.	TYP.	MAX.	UNIT	NOTE
Brightness	— ·	(60)	—	cd/m²	ILED=(80mA)
Brightness uniformity	_	· —	±40	%	Undermentioned (Note 1)

Ta=25°C VDD-VEE=23.0V Display data should be all "ON".


Note 1: Measurement of the following 9 places on the display.



Definition of the brightness tolerance.




# 8. INTERFACE TIMING CHART 8.1 INTERFACE TIMING CHART



## 8.2 TIMING CHARACTERISTICS


0°C ≦Ta ≦40°C, VDD=5V±5%

ITEM	SYMBOL	MIN.	TYP.	MAX.	UNIT
"CL2" Clock Frequency	fCL2	<b>-</b>	·	40	MHz
"CL2" Clock Pulse Width	tW	63	-	-	ns
Clock Rise , Fall Time	tr,tf	-	-	20	ns
Data Set Up Time	tDSU	50		-	ns
Data Hold Time	tDHD	:50	_	-	ns
CL1 Set Up Time	tLSU	80		· <b>-</b>	ns
CL1 Hold Time	tLC	80	-	-	ns
"FLM" Set Up Time	tSETUP	100	-	_	ns
"FLM" Hold Time	tHOLD	100		<u>-</u>	ns
"CL1" Pulse Width	tWC	125	-	-	ns



					· · · · · · · · · · · · · · · · · · ·		
KAOHSIUNG HITACHI ELECTRONICS CO.,LTD.	DATE	May.28,'07	Sh. No.	7B64PS	2708-ST12Q01L6ALZZ-2	PAGE	8-2/4

#### 8.3 POWER ON/OFF TIMING SEQUENCE




COMMENT	UNIT	MAX.	MIN.	SYMBOL
	ms	-	200	tDLD
(Note 1)	ms	-	0	tCH
	ms	_	0	tLDH
	ns	100	· <b>-</b>	tDOr
	ns	100		tDOf
(Note 2)	ms	_	20	tDLCr
	ms	<del>-</del>	0	tDLCf
	ms	_	20	tDLCs

Note 1 : Please keep the specified sequence because wrong sequence may cause permanent damage to the LCD panel.

Note 2 : HITACHI recommends you to use DOFF function.

display quality may deteriorate if you don't use DOFF function.

#### 8.4 POWER SUPPLY FOR LCM




Note 1 : C : 3.3  $\mu$  F (aluminum electrolytic capacitor)

VR: 10~20kΩ

Tr: 2SA673APKC (hfe=100, IC=500mA) or equivalent Tr.

KAOHSIUNG HITACHI	- - -		Sh.		
ELECTRONICS CO.,LTD.	DATE	May.28,'07	No.	7B64PS 2708-ST12Q01L6ALZZ-2   PAGE	8-3/4

## 8.5 DISPLAY PATTERN




# 9.3 INTERNAL PIN CONNECTION

CN1: Molex / 52103-1217(Suitable FPC: pitch 1.0mm 12 pins, 0.3t)

			11 (Saltable		1.011111 12 pino ; 0.00
INTER	FACE	PIN No.	SIGNAL	LEVEL	FUNCTION
LCM	I/F	~	FLM	Н	First Line Marker
		2	CL1	H→L	Data Latch
	·	3	CL2	H→L	Data Shift
		4	VDD	<del>-</del> .	Power Supply for Logic
	. 1	5	VSS		GND and Power Supply for LED(-)
		6	VEE	1	Power Supply for LC
		7	D0	•	Display Data
		8	D1	H/L	
		9	D2	11/6	
		10	D3	4	
*		11	DOFF	H/L	H:ON / L:OFF
		12	·VLED(+)	· .=	Power Supply for LED(+)

KAOHSIUNG HITACHI		NA 00 107	Sh.	7D04D0 0700 0740004L0AL77 0	DAGE	0.444
ELECTRONICS CO.,LTD.	DATE	May.28,'07	No.	7B64PS 2708-ST12Q01L6ALZZ-2	PAGE	0-4/4

# 9. DIMENSIONAL OUTLINE 9.1 DIMENSIONAL OUTLINE



Note 1 : CN1 : MOLEX/52103-1217.

Unit: mm Scale: NTS


	KAOHSIUNG HITACHI ELECTRONICS CO.,LTD.	DATE	May.28,'07	Sh. No.	7B63PS 2709-ST12Q01L6ALZZ-2	PAGE	9-1/1
--	-------------------------------------------	------	------------	------------	-----------------------------	------	-------

#### 10. APPEARANCE STANDARD

#### 10.1 APPEARANCE INSPECTION CONDITION

Visual inspection should be done under the following condition.


- (1) In the dark room.
- (2) With LED panel lighted with prescribed inverter circuit.
- (3) With eyes 25cm distance from LCM.
- (4) Viewing angle within 45 degrees from the vertical line to the center of LCD.



#### 10.2 DEFINITION OF EACH ZONE

A zone: Within the active area line specified at page 9-1/1 of this document.

B zone: Area between the window of bezel line and the active area line specified at page 9-1/1 of this document.



KAOHSIUNG HITACHI			Sh.		5.05	40.40
ELECTRONICS CO.,LTD.	DATE	May.28,'07	No.	7B64PS 2710-ST12Q01L6ALZZ-2	PAGE	10-1/3

# 10.3 APPEARANCE SPECIFICATION

\*) If the problem occurs about this item, the responsible person of both party (customer and HITACHI) will discuss more detail.


Scratches	*	-
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	*	-
$\begin{tabular}{ c c c c c c c c c c c c c c c c c c c$	*	-
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	. (	-
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	0	· <b>-</b>
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	0	-
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	0	· -
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	0	-
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$		
$\begin{tabular}{ c c c c c c c c c c c c c c c c c c c$		
$\begin{tabular}{ c c c c c c c c c c c c c c c c c c c$		
$\begin{tabular}{ c c c c c c c c c c c c c c c c c c c$	]	
Dark Spot $ \begin{array}{c ccccccccccccccccccccccccccccccccccc$		
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$		
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$		Ì
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$		
Average Diameter Maximum Number Space $ \begin{array}{c ccccccccccccccccccccccccccccccccccc$		
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$		
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	$\cup$	*
0.2 ≦D<0.33 8 10mm		
	. [	.
		.
The Whole Filamentous + Round = 10		.
Number   Filamentous + Round - 10		ĺ
	0	$\forall$
	*	$\exists$
	*	$\equiv$
Pinhole Average Diameter Maximum Number		-
D(mm) Acceptable		
	$\circ$	_
0.15 <d≦0.3 10<="" td=""><td><math>\sim</math> 1</td><td></td></d≦0.3>	$\sim$ 1	
C≦0.03 Ignore		

KAOHSIUNG HITACHI	DATE	14 00 107	Sh.	7D04D0 0740 0T40004L0AL77 0	DAGE	40.070
ELECTRONICS CO.,LTD.	DATE	May.28,'07	No.	7B64PS 2710-ST12Q01L6ALZZ-2	PAGE	10-2/3


No.	ITEM	CRITERIA				Α	В
	Contrast	Average	Contrast	Maximum	Minimum		
-	Irregularity	Diameter		Number	Space	}	
	(Spot)	D(mm)	•	Acceptable			
		D≦0.25	To Be	Ignore	. –	0	-
		0.25 <d≤0.35< td=""><td>Judged By</td><td>≦10</td><td>20mm</td><td></td><td></td></d≤0.35<>	Judged By	≦10	20mm		
		0.35 <d≦0.5< td=""><td>HITACHI Limit</td><td><b>≦4</b></td><td>20mm</td><td>].</td><td></td></d≦0.5<>	HITACHI Limit	<b>≦4</b>	20mm	].	
, .		0.5 < D	Sample	None	-		
C	Contrast	Width	Length	Maximum	Minimum		
D	Irregularity	D(mm)	L(mm)	Number	Space		.
	(Filamentous)			Acceptable			
		W≦0.25	L≦1.2	≦2	20mm		
		W≦0.2	L≦1.5	≦3	20mm		-
		W≦0.15	Ĺ≦2.0	≦3	20mm	<u>.</u>	
		W≦0.1	L≦3.0	<b>≦</b> 4	20mm		
, ,		The Whole Nu	mber	≦6			
	Rubbing Scratch	To Be Judged By HITACHI Standard					

## Note


(1) Definition of average diameter D



(2) Definition of length L and width W



(3) Definition of pinhole




KAOHSIUNG HITACHI ELECTRONICS CO.,LTD. DATE May.28,'07 No. 7B64PS 2710-ST12Q01L6ALZZ-2 PAGE 10-3/3

#### 11. PRECAUTION IN DESIGN

#### 11.1 MOUNTING METHOD

Since the module is so constructed as to be fixed by utilizing fitting holes in the printed circuit board as shown below, it is necessary to take consideration the following items on attachment to a frame.



- (1) Use of protective plate, made of an acrylic plate, etc. In order to protect a polarizer and LC cell.
- (2) To prevent the module cover from being pressed, the spacers between the module and the fitting plates should be longer than 0.5mm.
- (3) We recommend you to use protective spacer as figure for protecting LCD module from any kind of shock to your set.
- 11.2 LC DRIVING VOLTAGE(VEE) AND VIEWING ANGLE RANGE
  Setting VEE out of the recommended condition will be a cause for a change of viewing angle range.

KAOHSIUNG HITACHI			Sh.	7D04D0 0744 07400041 0A1 77 0	DAGE	44 4 10
ELECTRONICS CO.,LTD.	DATE	May.28,'07	No.	7B64PS 2711-ST12Q01L6ALZZ-2	PAGE	11-1/3

#### 11.3 CAUTION AGAINST STATIC CHARGE

As this module is provided with C-MOS LSIs, The care to take such a precaution as to grounding the operator's body is required when handling it.

#### 11.4 POWER ON SEQUENCE

Input signals should not be applied to LCD module before power supply voltage is applied and reaches to specified voltage ( $5V \pm 5\%$ ).

If above sequence is not kept, C-MOS LSIs of LCD modules may be damaged due to latch up problem.

#### 11.5 PACKING

- (1) No. Leaving products is preferable in the place of high humidity for a long period of time. For their storage in the place where temperature is 35°C or higher, special care to prevent them from high humidity is required. A combination of high temperature and high humidity may cause them polarization degradation as well as bubble generation and polarizer peel-off. Please keep the temperature and humidity within the specified range for use and storage.
- (2) Since upper/bottom polarizers tend to be easily damaged, They should be handled full with care so as not get them touched, pushed or rubbed.
- (3) As the adhesives used for adhering upper/bottom polarizers are made of organic substances which will be deteriorated by a chemical reaction with such chemicals as acetone, toluene, ethanol and isopropyl alcohol. The following solvents are recommended for use:

normal hexane

Please contact us when it is necessary for you to use chemicals.

- (4) Lightly wipe to clean the dirty surface with absorbent cotton waste or other soft material like chamois, soaked in the chemicals recommended without scrubbing it hardly. To prevent the display surface from damage and keep the appearance in good state, it is sufficient, in general, to wipe it with absorbent cotton.
- (5) Immediately wipe off saliva or water drop attached on the display area because its long period adherence may cause deformation or faded color on the spot.
- (6) Fogy dew deposited on the surface and contact terminals due to coldness will be caused for polarizer damage, stain and dirt on product. When necessary to take out the products from some place at low temperature for test, etc. It is required for them to be warmed up in a container once at the temperature higher than that of room.

- (7) Touching the display area and contact terminals with bare hands and contaminating them are prohibited, because the stain on the display area and poor insulation between terminals are often cause by being touched by bare hands. (there are some cosmetics detrimental to polarizers.)
- (8) In general the quality of glass is fragile so that it tends to be cracked or chipped in handling, specially on its periphery. Because be careful not to give it sharp shock caused by dropping down, etc.

#### 11.6 CAUTION FOR OPERATION

- (1) It is an indispensable condition to drive LCDs within the specified voltage limit since the higher voltage than the limit causes the shorter LCD life. An electrochemical reaction due to direct current causes LCDs undesirable deterioration, so that the use of direct current driver should be avoided.
- (2) Response time will be extremely delayed at lower temperature than the operating temperature range and on the other hand at higher temperature LCDs show dark bull color in them. However those phenomena do not mean malfunction or out of order with LCDs which will come back in the specified operating temperature range.
- (3) If the display area is pushed hard during operation, some font will be abnormally display but it resumes normal condition after turning off once.
- (4) A slight dew depositing on terminals is a cause for electrochemical reaction resulting in terminal open circuit. Usage under the relative condition of 40°C 50%RH or less is required.

#### 11.7 STORAGE

- In case of storing for a long period of time (for instance, for years) for the purpose of replacement use, the following ways are recommended.
- (1) Storage in a polyethylene bag with the opening sealed so as not to enter fresh air outside in it, and with no desiccant.
- (2) Placing in a dark place where neither exposure to direct sunlight nor light is, keeping temperature in the range from  $0^{\circ}$ C to  $35^{\circ}$ C.
- (3) Storing with no touch on polarizer surface by anything else. (It is recommended to store them as they have been contained in the inner container at the time of delivery from us.)

#### **11.8 SAFETY**


- (1) It is recommendable to crash damage or unnecessary LCDs into pieces and wash off liquid crystal by either of solvents such as acetone and ethanol, which should be burned up later.
- (2) When any liquid leaked out of a damage glass cell comes in contact with your hands, please wash it off well with soap and water.

KAOHSIUNG HITACHI	DATE	Sh.	700400 0744 07400041 081 77.0	DAGE	44 0/0
ELECTRONICS CO.,LTD.	DATE May 28,'07	No.	7B64PS 2711-ST12Q01L6ALZZ-2	PAGE	11-3/3

# 12. DESIGNATION OF LOT MARK

## 12.1 LOT MARK

Lot mark is consisted of 4 digits for production lot and 6 digits for production control.



YEAR	FIGURE IN LOT MARK
2007	7
2008	8
2009	9
2010	0
2011	1 :

i.			1			
	MONTH	FIGURE IN LOT MARK	MONTH	FIGURE IN LOT MARK		
	Jan.	01	Jul.	07		
	Feb.	02	Aug.	08		
	Mar.	03	Sep.	09		
	· Apr.	04	Oct.	10		
	May	05	Nov.	11		
	Jun.	06	Dec.	12		

<u> </u>
FIGURE IN LOT MARK
1
2
3
4
5

#### 12.2 REVISION

REV No.	ITEM	LOT No.	PRODUCTION CONTROL No.
_	-	_	000001~
А	Operating Life (40,000h)	7062T	000001~

12.3 Location of lot mark: On the back side of LCM

KAOHSIUNG HITACHI	DATE	May 00 107	Sh.	7B64PS 2712-ST12Q01L6ALZZ-2	D. 05	40-444
ELECTRONICS CO.,LTD.	DATE	May.28,07	No.	/B64PS 2/12-ST12Q01L6ALZZ-2	PAGE	12-1/1

#### 13. PRECAUTION FOR USE

- 13.1 A limit sample should be provided by the both parties on an occasion when the both parties agreed its necessity. Judgement by a limit sample shall take effect after the limit sample has been established and confirmed by the both parties.
- 13.2 On the following occasions, the handling of the problem should be decided through discussion and agreement between responsible persons of the both parties.
  - (1) When a question is arisen in the specifications.
  - (2) When a new problem is arisen which is not specified in this specifications.
- (3) When an inspection specifications change or operating condition change in customer is reported to HITACHI, and some problem is arisen in this specification due to the change.
- (4) When a new problem is arisen at the customer's operating set for sample evaluation in the customer site.

The precaution that should be observed when handling LCM have been explained above. If any points are unclear or if you have any request, please contact HITACHI.